# THECORNERGUARDSTORE<sup>TM</sup> **SUGGESTED SPECIFICATIONS - SECTION 10 26 13**

MODEL <u>CG-ANA-080-362.5-90</u>

# 36" x 2 1/2" x 2 1/2" - PRE-ANODIZED ALUMINUM CORNER GUARD

# Part 1 - GENERAL

### 1.01 **SUMMARY**

- **A.** This section includes the following types of wall protection systems:
  - 1. Corner Guards
- **B.** Related Sections
  - 1. Section 10 26 16 Bumper Guards
  - 2. Section 10 26 23 Protective Wall Covering
  - **3.** Door and Frame Protection
  - **4.** 09 22 00 Supports for Plaster and Gypsum Board

### 1.02 **REFERENCES**

**A.** American Society for Testing and Materials (ASTM)

# 1.03 SUBMITTALS

- **A.** General: Submit the following in accordance with conditions of contract and Division 1 specification section 01 33 00 "Submittal Procedures".
- **B.** Product data and detailed specifications for each system component and installation accessory required, including installation methods for each type of substrate.
- C. Shop drawings showing locations, extent and installation details of corner guards. Show methods of attachment to adjoining construction.
- **D.** Samples for verification purposes: Submit the following samples, as proposed for this work, for verification of guard.
- E. Product test reports from a qualified independent testing laboratory showing compliance of each component with requirements indicated.
- F. Maintenance data for wall protection system components for inclusion in the operating and maintenance manuals specified in Division 1.

# **QUALITY ASSURANCE**

- A. Installer qualifications: Engage an installer who has no less than 3 years experience in installation of systems similar in complexity to those required for this project.
- **B.** Manufacturer's qualifications: Not less than 5 years experience in the production of specified products and a record of successful in-service performance.
- C. Single source responsibility: Provide all components of the wall protection system manufactured by the same company to ensure compatibility of color, texture and physical properties.

# **DELIVERY, STORAGE AND HANDLING**

- A. Deliver materials to the project site in unopened original factory packaging clearly labeled to show manufacturer.
- **B.** Material must be stored flat.
- **C.** Handling: Take adequate measure to prevent damage to materials.

# 1.06 PROJECT CONDITIONS

A. Ambient Conditions: Do not install wall protection products until installation areas are enclosed and weatherproof. HVAC system must be operational and maintaining temperature at 65°-75°F (18°-24°C) for at least 72 hours prior to installation.

# Part 2 - PRODUCTS

# **MANUFACTURERS**

**A.** TheCornerGuardStore.com



2220 Fernbrook Lane North, Plymouth, MN 55447

11445 E Via Linda, Suite 2 #323, Scottsdale, AZ 85259

Tel: 800-516-0436

### 2.02 DESCRIPTION

**A.** Model: <u>CG-ANA-080-362.5-90</u> - 36" (914.4mm) x 2 1/2" (63.5mm) x 2 1/2" (63.5mm) x 90° Surface mounted pre-anodized aluminum corner guard with a 1/8" (3.2mm) radius corner. Construction adhesive included for standard installation. Available pre-drilled or pre-drilled and countersunk for use with mechanical fasteners. Angles other than 90° and 135° and wings other than 2 1/2" (63.5mm) are available.

# 2.03 MATERIALS

- **A.** Pre-Anodized Aluminum: Type 5005, .080 gauge, with a #4 satin finish.
- **B.** Adhesive: Polyurethane based construction adhesive.

# 2.04 FABRICATION

- **A.** Corner guards shall be factory formed from pre-anodized aluminum sheet.
  - 1. Lengthwise perimeter edges to include an optional nominal 10° return bend. (Wings Option)
  - **2.** Edge burrs shall be removed.
  - 3. Satin finish grain oriented parallel with length.
  - **4.** Single piece fabrication to 144" (3658) in length.

# 2.05 ACCESSORIES

- **A.** Mechanical Fasteners:
  - 1. For Optional Pre-drilled Holes: Stainless steel #8 x 1 1/4" Philips oval head wood screw with stainless steel cup washer.
  - **2.** For Optional Pre-drilled and Countersunk Holes: Stainless steel #8 x 1 1/4" Philips oval head wood screw.
  - 3. Tamper resistant fasteners available.

# **Part 3 - EXECUTION**

# 3.01 EXAMINATION

- **A.** Verification of conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper or timely completion.
  - 1. Do not proceed until unsatisfactory conditions have been corrected.

# 3.02 PREPARATION

- **A.** Surface preparation: Prior to installation, clean substrate to remove dirt, debris and loose particles. Perform additional preparation procedures as required by manufacturer's instructions.
- **B.** Protection: Take all necessary steps to prevent damage to material during installation as required in manufacturer's installation instructions.

# 3.03 INSTALLATION

**A.** Install the work of this section in strict accordance with the manufacturer's recommendations, using only approved mounting hardware, and locating all components firmly into position, level and plumb.

# 3.04 CLEANING

- **A.** General: Immediately upon completion of installation, clean material in accordance with manufacturer's recommended cleaning method.
- **B.** Remove surplus materials, rubbish and debris resulting from installation as work progresses and upon completion of work.

# 3.05 Protection

**A.** Protect installed materials to prevent damage by other trades. Use materials that may be easily removed without leaving residue or permanent stains.

